



CURTAIN DRAIN DETAIL




EVAPORATION-TRANSPIRATION TRENCH DETAIL


JAMES R. GILLS, P.E. County Drainage Engineer



SILT FENCE DETAIL

MAXIMUM DRAINAGE AREA (IN ACRES) TO 100 LINEAR FEET OF SILT FENCE	RANGE OF SLOPE FOR A PARTICULAR DRAINAGE AREA (IN PERCENT)
0.5	< 2%
0.25	≥ 2% BUT < 20%
0.125	> 20% RUT < 50%





HOUSE DETAIL SCALE: 1" = 10'

TEMPORARY SEEDING SPECIFICATIONS

3	4 BUSHEL
1	40 LB.
1	40 LB.
1	
1 1	40 LB. 40 LB. 40 LB.
3	2 BUSHEL
1	40 LB.
1	40 LB.
3	2 BUSHEL
1	40 LB.
	1

SOIL & WATER CONSERVATION NOTES


- 1. A STONE ACCESS DRIVE COMPLETE WITH UNDER LYING GEO-TEXTILE FABRIC (20 FEET WIDE AND 50 FEET LONG) FOR INGRESS AND EGRESS AT THE SITE SHALL BE INSTALLED. THIS DRIVE SHALL BE THE ONLY ENTRANCE AND EXIT TO THE SITE.
- SILT FENCE

 2. ALL SILT FENCE SHALL BE INSTALLED PRIOR TO ANY EARTHWORK ACTIVITIES AT THE SITE IN THE LOCATIONS SHOWN ON THE SITE PLAN AS WELL AS ALONG THE FRONT OF ANY LOT THAT SLOPES TOWARDS THE STREET. Date/32204
 - TEMPORARY SEEDING
 DISTURBED AREAS OF THE SITE THAT ARE TO REMAIN IDLE FOR MORE THAN TWENTY-ONE (21) DAYS SHALL BE PROPERLY SEEDED AND STRAW MULCHED WITHIN SEVEN (7) DAYS OF COMPLETION OF INITIAL GRADING. TEMPORARY SEEDING AND MULCHING OF A THRITY (30) FOOT STRIP OF THE ENTIRE FRONT OF THE LOT SHALL BE MAINTAINED ON THE SITE ONCE INITIAL GRADING IS COMPLETE.
 - 4. STABILIZATION OF CRITICAL AREAS WITHIN FIFTY (50) FEET OF ANY STREAM OR WETLAND SHALL BE COMPLETE WITHIN TWO (2) DAYS OF THE DISTURBANCE IF THE SITE IS TO REMAIN INACTIVE FOR LONGER THAN FOURTEEN (14) DAYS.
 - STRAW-MULCH SHALL BE APPLIED AT A RATE OF 1 BALE PER EVERY TEN (10) FEET OF CURB, AT A WIDTH OF THRITY (30) FEET OF THE ENTIRE LENGTH OF THE LOT. WOOD CHIPS MAY ALSO BE USED BUT MUST BE SPREAD A MINIMUM DEPTH OF FOUR (4) INCHES OVER THE THRITY-FOOT WIDTH AND MUST BE ACCOMPANIED BY A PROPERLY INSTALLED SILT FENCE.
 - 6. MAINTENANCE EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED EVERY (7) SEVEN DAYS OR WITHIN 24 HOURS OF A 0.5" OR GREATER RAINFALL EVENT. NECESSARY REPAIRS SHALL BE MADE AT THIS TIME.
 - ALL EROSION AND SEDIMENT CONTROL SPECIFICATIONS, APPLICATIONS, AND TIMETABLES ARE BASED ON THE DESCRIPTIONS AND STANDARDS OF THE OHIO DEPARTMENT OF NATURAL RESOURCES "RAINWATER AND LAND DEVELOPMENT MANUAL" AND CAN BE FOUND IN THE LAKE COUNTY EROSION AND SEDIMENT CONTROL RULES AS ADOPTED DECEMBER 21, 1999.
 - THE SPECIFIED EROSION AND SEDIMENT CONTROL STANDARDS ARE GENERAL GUIDELINES AND SHALL NOT LIMIT THE RIGHT OF THE COUNTY TO IMPOSE, AT ANY TIME, ADDITIONAL, MORE STRINGENT REQUIREMENTS.

SITE PLAN DATA

- 1.) ALL SURVEY DATA SHOWN IS BASED ON A SITE SURVEY FOR TOM REED GENERAL CONTRACTOR OF S/L 17 & S/L 18 PREPARED BY VILLAGE SURVEYING CO. PERFORMED BY THOMAS M. COFFMAN., P.S. OHIO #6857 DATED MARCH 12 OF
- 2.) BENCHMARK USED FOR THE PROJECT IS A NAIL IN THE EXISTING TREE ON THE WEST SIDE OF PALISADES DRIVE APPROX. 45 L.F. WEST OF THE € OF PALISADES DRIVE AND APPROX. 212 L.F. NORTH OF THE NORTHWEST CORNER OF S/L 18. ELEVATION OF THE NAIL. ⇒ 104.33
- 3.) OWNER: TOM REED GENERAL CONTRACTING, INC. P.P.N.: 01A-029A-00-018-0 (S/L 18)
- 4.) SEE ARCHITECTURAL PLANS FOR FINAL BUILDING DIMENSIONS AND DETAILS

		,		
Rev.	Description	Date	By	E
~	REVISED AS PER GERALD NORRIS OF LCHD	3/16/04	1	5



Drawn By: BKG Checked By: Approved By: Date: 3/16/04

Horiz. 1"= 20' Scale: Vert. 1"=N/A Sheet No. Of

Filename: 04-011/DB

· :