IPF

IPF

68.78

IPF

68.78

N-87°02'50"E
68.42'

IPS

LAKE
WATER LEV. 96.60

TOP-LAKE BANK

96.5

1450 Lin. Ft.
of Dike

208.63

DIST. BOX

2-1000 Gl's
TANKS

SWALE

EXIST.
HOUSE

97.5

98.0

15'

24'

HOUSE
F.F. 101.00

38'

5'

WELL

50' SET BRK

B.M.
POLE P.C. #5001

EXIST. PAVEMENT

EDGEWOOD DRIVE 40'
R/W

S-79°12'-W
200.00'

S-79°12'-W
65.12'

IPF

IPF

70'

R/W

70'

EXIST.
PAVEMENT

SPRING LAKE BLVD. SOUTH 40'
R/W

ZP #1434

Conditionally Approved
and/or noted
THOMAS P. GILLESS, P.E.
Lake County Engineer

By JWK Date 4-8-94

NOTE:
1. B.M. POLE P.C. #6001
NAIL IN POLE
ASSUMED ELEV. 100.00
2. ELEVATIONS UNDERLINED ARE
PROPOSED ELEVATIONS.
3. F.F. = FINISHED FLOOR ELEVATION.

"AS BUILT CERTIFICATION"

I HEREBY CERTIFY THAT THE CIRCLED GRADES ARE
EXIST. FINISH GRADES CHECKED IN FIELD ON _____
SURVEY IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

_____
REG. SURVEYOR No.

SITE PLAN
FOR
MR. WILLIAMS
PERRY TOWNSHIP LAKE COUNTY, OHIO

Colpetzer · Woods Consultants, Inc.
CONSULTING ENGINEERS AND SURVEYORS
PAINESVILLE, OHIO 44077

DATE MAR.
SCALE 1"=
DRAWN BY
CH'K'D BY
F.B.#

4093-1-2